



NORFOLK

Department of City Planning
Bureau of Environmental Services

Notice:

Demolition Contractors working in the City of Norfolk.

Due to the problem of sites being left un-stabilized and sediment eroding offsite, the City will be strictly enforcing the Erosion and Sediment Control Ordinance on demolitions.

Demolition Contractors are responsible for:

1. Completing the agreement in lieu of an erosion and sediment control plan form and identifying a responsible land disturber for the site.
2. Establishing and maintaining silt fences around the perimeter of demolition sites unless concrete or pavement is not removed from site.
3. Any sediment or debris that leaves the site must be swept up daily.
4. **Seeding and stabilizing any exposed soils after demolition is complete**

If you have any questions, comments, or concerns contact -

Odell Glenn: 664-4365 or odell.glenn@norfolk.gov

Seamus McCarthy: 664-4363 or seamus.mccarthy@norfolk.gov



City of Norfolk

City of Norfolk Standard Erosion & Sediment Control Notes

1. Unless otherwise indicated, all vegetative and structural erosion and sediment control practices will be constructed and maintained according to minimum standards and specifications of the Virginia Erosion and Sediment Control Handbook (3rd Edition, 1992) and the City of Norfolk erosion and sediment control ordinance.
2. The contractor shall contact the City of Norfolk, Bureau of Environmental Services (664-4368) at least 48 hours prior to any land disturbing activity (including demolition) so that a preconstruction conference can be scheduled.
3. The contractor shall apply permanent or temporary soil stabilization to all denuded or disturbed areas within 7 days after final grade is reached on any portion of the site. Soil stabilization must also be applied to denuded or disturbed areas which may not be at final grade but which will remain undisturbed for longer than 14 days. Soil stabilization measures include vegetative establishment, mulching and the early application of gravel base material on areas to be paved.
4. All erosion and sediment control measures are to be placed prior to or as the first step in construction.
5. The contractor shall inspect all erosion control measures periodically and after each runoff producing rainfall event. Any necessary repairs to maintain the effectiveness of the erosion control devices and cleanup of sedimentation are the responsibility of the contractor and shall be made immediately.
6. The contractor shall limit site access by construction vehicles to entrances protected by a stone construction entrance (VESCH Std. & Spec. 3.02) or an approved comparable control measure. Sediment shall be removed from paved areas on a daily basis.
7. Stock piles of soil and other erodible materials shall be stabilized or protected with sediment trapping measures. The contractor is responsible for the temporary protection and permanent stabilization for stockpiles on site as well as for materials transported from the project site.
8. The contractor shall monitor and take precautions to control dust including (but not limited to) use of water, mulch, or chemical dust adhesives and control of construction site traffic.
9. Effluent from de-watering operations shall be filtered or passed through an approved sediment trapping device, or both, and discharged in a manner that does not adversely affect adjacent properties, wetlands, waterways or the storm drainage system.
10. The contractor is responsible for installation and maintenance of any additional control measures necessary to prevent erosion and sedimentation as determined necessary by the plan approving authority.
11. Temporary erosion and sediment control measures are not to be removed until all disturbed areas are stabilized. After stabilization is complete, all measures shall be removed within 30 days. Trapped sediment shall be spread and seeded.