

PROJECT: INFRASTRUCTURE IMPROVEMENTS

LOCATION

West 38th Street, between Bluestone Avenue and Parker Avenue

PROJECT INFORMATION

This project will enhance and improve the West 38th Street Median; the ADA ramps will be replaced, all median curb will be replaced, and the diseased median trees will be replaced with healthier and more diverse tree species.

SCOPE OF WORK

- Replace 2 ADA ramps on the West side of Blue Stone Avenue at the median, cut back median curb for cross walk, and add crosswalk striping between the new ramps across West 38th Street.
- Remove all 3 blocks of existing curb in median.
- Install a new 6-inch concrete curb around the entire median.
- Remove poor soil from the median, as needed.
- Remove existing trees from the median, with the exception of a few, and replace with new trees to provide a diversity of species.
- The new tree species (Upright European Hornbeam) grows to a height of 30-35 feet, with a spread of 15 feet. The tree canopy is low, does not require a lot of maintenance, and can live up to 120 years.
- Fill new median with soil and mulch.
- Add new yellow pavement markings around the new median.

PROJECT STATUS

COMPLETE

PROJECT SCHEDULE

Start date: Late 2019

Completion date: Mid 2020

PROJECT COST

\$275,000

CIVIC LEAGUE/TASK FORCE

- Lambert’s Point Civic League
- Ward 2
- Superward 7

PROJECT CONTACTS

PROJECT MANAGER

David Pfiffer, Public Works

David.Pfiffer@norfolk.gov

757-664-4638

CONSTRUCTION CONTRACTOR

Site Work South

CONSTRUCTION INSPECTOR(S)

Duncan Howard

Duncan.Howard@Norfolk.gov

757-664-4677

